

ANSIBLE PROJECT ON AWS

You are a Devops Engineer and the organization you are working on needs to set up two configuration management server groups. One for Apache another for Nginx. Being a Devops Engineer it is your task to deal with this configuration management issue.

Let us see the tasks that you need to perform using Ansible.

1. Create two Server Groups. One for Apache and another for Nginx.
2. Push two html files with their server information.

Make sure that you don't forget to start the services once the installation is done. Also send post installation messages for both the server groups.

Using Ansible Roles accomplish the above the tasks.

Also, once the Apache server configuration is done you need to install Java on that server group using ansible role in a playbook.

WHAT IS ANSIBLE?


Ansible is an automation and orchestration tool popular for its simplicity of installation, ease of use in what concerns the connectivity to clients, its lack of agent for ansible clients and the multitude of skills.

Ansible supports the deployment and infrastructure management phases of the DevOps lifecycle, automating such tasks as configuration management, infrastructure provisioning, and application deployment.
















Ansible functions by connecting via SSH to the clients, so it doesn't need a special agent on the client-side, and by pushing modules to the clients. The modules are then executed locally, on the client-side, and the output is pushed back to the Ansible server.

Since it uses SSH, it can very easily connect to clients using SSH-Keys, simplifying though the whole process. Client details, like hostnames or IP addresses and SSH ports, are stored in files called inventory files. Once you have created an inventory file and populated it, ansible can use it.

How Ansible Will Work In This Project



Step 1. Configure 3 VMs on AWS. One ansible (master) and two worker nodes (apache (node1) and nginx (node2))

	ansible	i-01c366bb1332e2d4f	 Running	 	t2.micro	-	No alarms		us-east-2c	ec2-3-16-155-57.us-eas...	3.16.155.57	-
	node1	i-0068feb4867dcc655	 Running	 	t2.micro	-	No alarms		us-east-2c	ec2-3-133-86-114.us-e...	3.133.86.114	-
	node2	i-0c51736a6a71bf0c4	 Running	 	t2.micro	-	No alarms		us-east-2c	ec2-18-217-54-29.us-e...	18.217.54.29	-

Step 2. Install ansible by including the following commands in a script file, ansible.sh in the master (ansible) and run script file via bash ansible.sh

Check node1 and node2 to verify that python3 --version is installed.

```
sudo apt update
sudo apt install software-properties-common
sudo apt-add-repository --yes --update ppa:ansible/ansible
sudo apt install ansible
```

Step 3. ssh connection into node1 and node2 from the master. See commands below

```
cd
cd .ssh
ls
ssh-keygen
cat id_rsa.pub
```

On node:

```
cd .ssh
sudo nano authorized_key
```

Note: paste key save & exit

Step 4. Check ssh connection – both were successful

ssh [ubuntu@3.133.86.114](https://3.133.86.114) – this is public ip address for node1

ssh [ubuntu@18.217.54.29](https://18.217.54.29) – this is public ip address for node2

Step 5. Configure host file for two server groups.

Change to ansible directory and the host file

```
cd /etc/ansible
```

```
ls
```

```
Sudo nano hosts
```

Create two server groups.

-- Get apacheserver (node1) private ip address using hostname -f and paste in host file on master

```
[apacheserver]
```

```
ip-172-31-39-50.us-east-2.compute.internal
```

-- Get nginxserver (node2) private ip address using hostname -f and paste in host file on master

```
[nginxserver]
```


```
ip-172-31-38-139.us-east-2.compute.internal
```

--Save & Exit

Step 6. Check to see if ansible can connect to the other two machines (node1 & node2) using the ping command

From the ansible directory cd /etc/ansible

```
ansible -m ping all
```



```
ubuntu@ip-172-31-43-215:/etc/ansible$ ansible -m ping all
ip-172-31-38-139.us-east-2.compute.internal | SUCCESS => {
  "ansible_facts": {
    "discovered_interpreter_python": "/usr/bin/python3"
  },
  "changed": false,
  "ping": "pong"
}
ip-172-31-39-50.us-east-2.compute.internal | SUCCESS => {
  "ansible_facts": {
    "discovered_interpreter_python": "/usr/bin/python3"
  },
  "changed": false,
  "ping": "pong"
}
ubuntu@ip-172-31-43-215:/etc/ansible$
```

Step 7. Create role1 & role2 using the command:

```
ubuntu@ip-172-31-43-215:/etc/ansible/roles$ sudo ansible-galaxy init role1
- Role role1 was created successfully
ubuntu@ip-172-31-43-215:/etc/ansible/roles$
```

Navigate to tasks directory and create multiple files

Roles:

Role1: apacheserver

- Main.yml – currently there is nothing in this file
- Install.yml – to install apache2
- Config.yml – taking the file from the location and pasting it in the location /var/www/html
- Service.yml – make the apache service running
- Java.yml – install java

Files

- Index.html -----> /var/www/html

Create the following files under tasks using sudo nano <file_name> (where file name is as shown below)

sudo nano **install.yml**

- name: Install Apache2
apt: name=apache2 state=latest
become: true

sudo nano **config.yml**

- name: Install Apache2
copy: src=index.html dest=/var/www/html
become: true

sudo nano **service.yml**

- name: service
service: name=apache2 state=started
become: true

Step 8. Create a playbook

Go to /etc/ansible/

Sudo nano playbook.yml

playbook.yml


- hosts: apacheserver

roles:

- role1

Step 9. Go to main.yml and attach the above files so playbook will read them

/etc/ansible/roles/role1/tasks



```
ubuntu@ip-172-31-43-215:/etc/ansible/roles/role1/tasks$ ls
config.yml  install.yml  main.yml    service.yml
ubuntu@ip-172-31-43-215:/etc/ansible/roles/role1/tasks$
```

Step 10. Run playbook

etc/ansible

Using command: ansible-playbook playbook.yml



```
PLAY [apacheserver] *****
TASK [Gathering Facts] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]

TASK [role1 : Install Apache2] *****
changed: [ip-172-31-39-50.us-east-2.compute.internal]

TASK [role1 : Install Apache2] *****
An exception occurred during task execution. To see the full traceback, use -vvv. The error was: If you are using a module and expect the file to exist on the remote, see the remote_src option
fatal: [ip-172-31-39-50.us-east-2.compute.internal]: FAILED! => {"changed": false, "msg": "Could not find or access 'index.html'\nSearched in:\n\t/etc/ansible/roles/role1/files/index.html\n\t/etc/ansible/roles/role1/index.html\n\t/etc/ansible/roles/role1/tasks/files/index.html\n\t/etc/ansible/roles/role1/tasks/index.html\n\t/etc/ansible/files/index.html\n\t/etc/ansible/index.html on the Ansible Controller.\nIf you are using a module and expect the file to exist on the remote, see the remote_src option"}

PLAY RECAP *****
ip-172-31-39-50.us-east-2.compute.internal : ok=2    changed=1    unreachable=0    failed=1    skipped=0    rescued=0    ignored=0


ubuntu@ip-172-31-43-215:/etc/ansible$
```

The above error requires me to update the machines (master, node1, & node2)


```
PLAY [apacheserver] *****
TASK [Gathering Facts] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : Install Apache2] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : Install Apache2] *****
changed: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : service] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
PLAY RECAP *****
ip-172-31-39-50.us-east-2.compute.internal : ok=4    changed=1    unreachable=0    failed=0    skipped=0    rescued=0    ignored=0
ubuntu@ip-172-31-43-215:/etc/ansible$
```

Step 13. Check from the browser

Node1 public IP address. The playbook runs successfully!



Step 14. Download CSS Template & then deploy

/etc/ansible/roles/role1/files

/etc/ansible/roles/role1/files\$ sudo wget <https://www.free-css.com/assets/files/free-css-templates/download/page276/spicy.zip>

/etc/ansible/roles/role1/files\$ sudo apt install unzip

/etc/ansible/roles/role1/files\$ sudo unzip spicy.zip

Run playbook again

Using command: ansible-playbook playbook.yml


```
PLAY [apacheserver] *****
TASK [Gathering Facts] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : Install Apache2] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : Install Apache2] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : service] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
PLAY RECAP *****
ip-172-31-39-50.us-east-2.compute.internal : ok=4    changed=0    unreachable=0    failed=0    skipped=0    rescued=0    ignored=0
ubuntu@ip-172-31-43-215:/etc/ansible$
```

We have only specified to copy index.html in the config.yml file so need to change to:

```
- name: Install Apache2
  copy: src=spicy dest=/var/www/html
  become: true
```

/etc/ansible


Run playbook again

Using command: ansible-playbook playbook.yml

```
PLAY [apacheserver] *****
TASK [Gathering Facts] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : Install Apache2] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : Install Apache2] *****
changed: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : service] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
PLAY RECAP *****
ip-172-31-39-50.us-east-2.compute.internal : ok=4    changed=1    unreachable=0    failed=0    skipped=0    rescued=0    ignored=0
ubuntu@ip-172-31-43-215:/etc/ansible$
```

Changes have occurred as expected.

Step 15. Check results from browser which is working on node1 (worker node)



Playbook ran successfully!

Step 16. Now add role2 (node2)

```
ubuntu@ip-172-31-43-215:/etc/ansible/roles/role2/tasks$ ls
main.yml
```

```
/etc/ansible/roles/role2/tasks$ sudo nano install.yml
```

```
---
- name: Install nginx
  apt: name=nginx state=latest
  become: true
```

```
/etc/ansible/roles/role2/tasks$ sudo nano config.yml
```

```
---
- name: config indexhtml
  copy: src=index.html dest=/var/www/html
  become: true
```

```
/etc/ansible/roles/role2/tasks$ sudo nano service.yml
```

```
---
```

```
- name: service
  service: name=nginx state=started
  become: true
```

```
/etc/ansible/roles/role2/tasks$ sudo nano main.yml
```

```
---
```

```
# tasks file for role2
- include : install.yml
- include : config.yml
- include : service.yml
```

```
/etc/ansible/roles/role2/files$ sudo nano index.html
```

How's everyone doing?

Now we need to make changes in the playbook

```
/etc/ansible$ sudo nano playbook.yml
```

```
---
```

```
- hosts: apacheserver
  roles:
    - role1
- hosts: nginxserver
  roles:
    - role2
```

Step 17. Now run playbook

/etc/ansible\$ ansible-playbook playbook.yml

```
PLAY [apacheserver] *****
TASK [Gathering Facts] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : Install Apache2] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : Install Apache2] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : service] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
PLAY [nginxserver] *****
TASK [Gathering Facts] *****
ok: [ip-172-31-38-139.us-east-2.compute.internal]
TASK [role2 : Install nginx] *****
changed: [ip-172-31-38-139.us-east-2.compute.internal]
TASK [role2 : config indexhtml] *****
changed: [ip-172-31-38-139.us-east-2.compute.internal]
TASK [role2 : service] *****
ok: [ip-172-31-38-139.us-east-2.compute.internal]
PLAY RECAP *****
ip-172-31-38-139.us-east-2.compute.internal : ok=4    changed=2    unreachable=0    failed=0    skipped=0    rescued=0    ignored=0
ip-172-31-39-50.us-east-2.compute.internal : ok=4    changed=0    unreachable=0    failed=0    skipped=0    rescued=0    ignored=0
ubuntu@ip-172-31-43-215:/etc/ansible$
```

Two changes occurred as expected.

Step 18. Install Java

ubuntu@ip-172-31-43-215:/etc/ansible/roles/role1/tasks\$ ls
config.yml install.yml main.yml service.yml

/etc/ansible/roles/role1/tasks\$ sudo nano install java.yml

```
---
- name: Install java
  apt: name=openjdk-11-jdk state=latest
  become: true
```

/etc/ansible/roles/role1/tasks\$ sudo nano main.yml

```
---
# tasks file for role1
- include: install.yml
- include: config.yml
- include: service.yml
- include: java.yml
```

Need an html file for role2:

```
ubuntu@ip-172-31-43-215:/etc/ansible/roles/role2/files
```

Get template from internet

```
ubuntu@ip-172-31-43-215:/etc/ansible/roles/role2/files$ sudo wget https://www.free-css.com/assets/files/free-css-templates/download/page278/buzzed.zip
```

Install & Unzip file:

```
/etc/ansible/roles/role1/files$ sudo apt install unzip
```

```
/etc/ansible/roles/role1/files$ sudo buzzed.zip
```

```
ubuntu@ip-172-31-43-215:/etc/ansible/roles/role2/tasks$ sudo nano config.yml
```

change config.yml to:

```
---  
- name: config indexhtml  
  copy: src=buzzed-html-template dest=/var/www/html  
  become: true
```

Step 19: Run playbook again

```
ubuntu@ip-172-31-43-215:/etc/ansible$ ansible-playbook playbook.yml
```


```

PLAY [apache2server] *****
TASK [Gathering Facts] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : Install Apache2] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : Install Apache2] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : service] *****
ok: [ip-172-31-39-50.us-east-2.compute.internal]
TASK [role1 : Install java] *****
changed: [ip-172-31-39-50.us-east-2.compute.internal]
PLAY [nginxserver] *****
TASK [Gathering Facts] *****
ok: [ip-172-31-38-139.us-east-2.compute.internal]
TASK [role2 : Install nginx] *****
ok: [ip-172-31-38-139.us-east-2.compute.internal]
TASK [role2 : config indexhtml] *****
changed: [ip-172-31-38-139.us-east-2.compute.internal]
TASK [role2 : service] *****
ok: [ip-172-31-38-139.us-east-2.compute.internal]
PLAY RECAP *****
ip-172-31-38-139.us-east-2.compute.internal : ok=4    changed=1    unreachable=0    failed=0    skipped=0    rescued=0    ignored=0
ip-172-31-39-50.us-east-2.compute.internal : ok=5    changed=1    unreachable=0    failed=0    skipped=0    rescued=0    ignored=0


```

Two changes occurred as expected.

Step 20: Results of node2



How's everyone doing?



Node2 playbook ran successfully!